



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

**Bid Receiving - PWGSC / Réception des soumissions -
TPSGC**

11 Laurier St. / 11, rue Laurier

Place du Portage, Phase III

Core 0B2 / Noyau 0B2

Gatineau, Québec K1A 0S5

Bid Fax: (819) 997-9776

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

**Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution

Electrical & Electronics Products Division

11 Laurier St./11, rue Laurier

7B3, Place du Portage, Phase III

Gatineau, Québec K1A 0S5

| | |
|--|---|
| Title - Sujet CCTV for the visit booths at RRC | |
| Solicitation No. - N° de l'invitation 21120-185773/A | Amendment No. - N° modif. 001 |
| Client Reference No. - N° de référence du client 21120-18-2685773 | Date 2017-11-27 |
| GETS Reference No. - N° de référence de SEAG PW-\$\$HN-467-73577 | |
| File No. - N° de dossier hn467.21120-185773 | CCC No./N° CCC - FMS No./N° VME |
| Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-12-06 | Time Zone Fuseau horaire Eastern Standard Time EST |
| F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/> | |
| Address Enquiries to: - Adresser toutes questions à: Dubé, Robert | Buyer Id - Id de l'acheteur hn467 |
| Telephone No. - N° de téléphone (873) 469-3936 () | FAX No. - N° de FAX (819) 953-4944 |
| Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: | |

Instructions: See Herein

Instructions: Voir aux présentes

| | |
|--|--|
| Delivery Required - Livraison exigée | Delivery Offered - Livraison proposée |
| Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur | |
| Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur | |
| Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie) | |
| Signature | Date |

Solicitation No. - N° de l'invitation
21120-185773/A

Amd. No. - N° de la modif.
001

Buyer ID - Id de l'acheteur
hn467

Client Ref. No. - N° de réf. du client
21120-185773

File No. - N° du dossier
hn467.21120-185773

CCC No. /N° CCC - FMS No. /N° VME

AMENDMENT #001

This amendment solicitation is raised to:

- 1) Provide Meeting Minutes of the mandatory site visit on November 16th, 2017; and
- 2) Answer question(s) from the industry.

1) During bidders' visits to Regional reception Centre Institution, observations were made about various elements which raised some questions. Clarification would be useful here in order to standardize the information provided to bidders and eliminate any possible ambiguity.

Additional information:

- A. The equipment cabinet must be installed in the basement on either a concrete or metal base in order to provide a levelled surface. If a metal base is selected, the base must be anchored to the existing concrete floor. The cabinet must be attached to the base with bolts. Wood is not acceptable material for the base.
- B. The electrical circuit for the equipment cabinet must come from the ELP-5E located in the basement 15 meters away from the equipment cabinet planned location. The contractor is responsible for the wiring and the breaker installation in the electrical panel in accordance with the Canadian Electrical Code.
- C. As indicated in Statement of technical Requirements section 4.4.10, connection to the electrical must be done at zero energy. The contractor must schedule that activity with the institution.
- D. Inside the 8 visit booths, conduits coming from the cameras towards the basement must be secured with clamps using double anchoring and anti-vandal screws. Junction boxes are not permitted in the 8 visit booths.
- E. The Omnicast software version currently being used is 4.8.
- F. In the equipment cabinet, equipment installation must be start from the bottom of cabinet. The uninterruptible power supply and its battery must be installed at the lowest point. Free space can be left between the equipment to allow for heat dissipation and in accordance with manufacturer's specifications. An arrangement drawing must be submitted by the contractor to the Chief, Electronic Systems Maintenance for approval.
- G. The Network video user station (NVUS) must provide viewing of images coming from the 8 visit booths only. No other image must be accessible by this NVUS. No storage is permitted with this NVUS. The computer must be installed in the equipment cabinet. The display and mouse must be installed in the control room (room B-111). NVUS shut-down form the monitor located in the control room is not allowed.

Solicitation No. - N° de l'invitation
21120-185773/A

Amd. No. - N° de la modif.
001

Buyer ID - Id de l'acheteur
hn467

Client Ref. No. - N° de réf. du client
21120-185773

File No. - N° du dossier
hn467.21120-185773

CCC No. /N° CCC - FMS No. /N° VME

-
- H. CAT6 cables coming from the cameras must be terminated on a patch-panel installed in the equipment cabinet.
- I. The contractor must demonstrate that at least one of his team members has an Omnicast certification.
- J. In the basement, rigid conduits installed by the contractor must be attached to the ceiling above vent plenums and plumbing.
- K. Image streams coming from the 8 cameras must be forwarded to the archivers located in the Common Equipment Room (CER). The contractor must modify the existing system to achieve this requirement. Video archiving is currently achieved using Pivot 3 servers.
- L. On a video loss from any of the 8 cameras, an alarm must be programmed in Omnicast in order to be displayed on the Facility Alarm Annunciation System (FAAS).
- M. With the addition of cameras in Omnicast, the contractor must add the required licenses.

2) Questions from the industry:

| | | |
|----|--|---|
| 1. | Q1. For the concrete slab drilling under the visit booth floor, is it a double rebar or a regular rebar concrete floor? | A1. The concrete slab contains a single rebar. |
|----|--|---|

ALL OTHER TERMS AND CONDITIONS OF THE BID SOLICITATION REMAIN UNCHANGED