

Addendum No. 1

Solicitation No. EQ754-202018 Amendment No. - 002

HOG'S BACK FIXED BRIDGE & DAM REHABILITATION BUNDLE 2
BRIDGE REPLACEMENT
RIDEAU CANAL
OTTAWA, ONTARIO

Project Specification Section 01 22 01 – Measurement and Payments.

Following changes are made to the project specification Section 01 22 01 – Measurement and Payment.

Remove specification section 01 22 01, paragraph 1.6.8.1:

“Item No. U8 – Cast-in-place Concrete: Cast-in-place Concrete to be measured and paid by unit price of cubic metres of concrete placed and accepted in-place. Unit price for cast-in-place concrete to include all formwork, scaffolding, platforms and curing required to complete the work. Unit price includes the drilling installation of rebars to existing concrete using epoxy adhesive. Cast-in-place concrete for bridge deck, multi-use pathway and curb located on the bridge deck (between the bridge expansion joints) to be excluded from this item.”

Section 01 22 01, Paragraph 1.6.8.1 is replaced by following:

“Item No. U8 – Cast-in-place concrete: Cast-in-place Concrete to be measured and paid by unit price of cubic meters of concrete placed and accepted in-place. Unit price for cast-in-place concrete to include all formwork, scaffolding, platforms and curing required to complete the work. Cast-in-place concrete for bridge deck, multi-use pathway and curb located on the bridge deck (between the bridge expansion joints) to be excluded from this item.”

Remove specification section 01 22 01, paragraph 1.6.10.1:

“Item No. U10 – Dowels: Dowels for cast-in-place concrete to be measured and paid at unit price for each dowel supplied, installed and accepted in place including labour, materials, drilling and epoxy adhesive. Dowels required for bridge deck and multi-use pathway and curb located on the bridge deck (between the bridge expansion joints) is excluded from this item.”

Section 01 22 01, Paragraph 1.6.10.1 is replaced by following:

“Item No. U10 – Dowels: Dowels and anchors for cast-in-place concrete to be measured and paid at unit price for each dowel and anchor installed and accepted in place including labour, materials, drilling and epoxy adhesive. Reinforcing material for the dowels and anchors are to be measured as set out with Unit Rate Item No. U7 – Reinforcing Steel. Dowels required for bridge deck and multi-use pathway and curb located on the bridge deck (between the bridge expansion joints) is excluded from this item.”